


| 01.02.01 MANTENIMIENTO DE TRANSITO Y SEGURIDAD VIAL                            |       |          |                |          |                  |
|--|-------|----------|----------------|----------|------------------|
| DESCRIPCION  | UND   | CANTIDAD | HH             | CANTIDAD | PARCIAL          |
| <b>MANO DE OBRA</b>  |       |          |                |          |                  |
| Banderillero y/o sefialero (PEON)  | MES   | 3.00     | 18.65          | 1,200.00 | 67,140.00        |
| <b>TOTAL</b>   |       |          |                |          | <b>67,140.00</b> |
| MATERIALES   | UND   | CANTIDAD | PRECIO SIN IGV | % PART.  | PARCIAL SIN IGV  |
| SEfAL PC-2   | und   | 40       | 72.28          | 1.00     | 2,891.20         |
| SEfAL PC-7   | und   | 40       | 70.35          | 1.00     | 2,814.00         |
| SEfAL PC-11  | und   | 40       | 41.50          | 1.00     | 1,660.00         |
| SEfAL PC-12  | und   | 49       | 50.85          | 1.00     | 2,491.65         |
| SEfAL X-1  | und   | 49       | 50.85          | 1.00     | 2,491.65         |
| SEfAL P-47   | und   | 49       | 70.34          | 1.00     | 3,446.66         |
| BARRERAS O TRANQUERAS 1.20x1.50  | und   | 46       | 41.54          | 1.00     | 1,910.83         |
| PARANTE DE MADERA-CACHACOS BASE DE CONCRETO PARA ZONA DE OBRA( h=1.20m)        | und   | 300      | 12.50          | 1.00     | 3,750.00         |
| PARANTE DE MADERA-CACHACOS BASE DE CONCRETO PARA DESVIO Y PREVENTIVA( h=1.50m) | und   | 120      | 16.95          | 1.00     | 2,034.00         |
| PALETAS DE SEGURIDAD DE PARE Y SIGA 45X45 cm                                   | und   | 20       | 23.74          | 1.00     | 474.80           |
| CONOS DE 70cm DE ALTO  | und   | 35       | 43.46          | 1.00     | 1,521.10         |
| CHALECOS DE SEGURIDAD CIJ  | und   | 20       | 50.17          | 1.00     | 1,003.40         |
| CINTA DE SEGURIDAD (400m)  | ROLLO | 50       | 48.76          | 1.00     | 2,438.00         |
| MALLA DE SEGURIDAD (50yd)  | ROLLO | 50       | 36.00          | 1.00     | 1,800.00         |
| ESCOBAS DE PAJA  | und   | 20       | 18.45          | 1.00     | 369.00           |
| <b>TOTAL</b>   |       |          |                |          | <b>31,096.29</b> |
| <b>TOTAL</b>   |       |          |                |          | <b>98,236.29</b> |

  
**CHRISTIAN TOMAS GUERRERO CARDENAS**  
 Ingeniero Civil  
 CIP N° 238605

  
**WINNER CONSTRUCCIONES EIRL**  
**Imer Ramos Nolasco**  
 DNI N° 22511504  
 TITULAR GERENTE